

1 080302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,768-0000
NE NE, SEC. 21, T 22 S, R 12 W/EK
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6166

Lease Name Ukens Well # 1

Operator: Chew Oil & Gas Co.

County Stafford 121.20

Name & Address 117 W. Main, Box 90

Well Total Depth 3729 feet

Lyons, KS 67554

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 7 Month: January Year: 19 85

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 816-938-2457

were: 5 1/2" set at 3729' PBTD 3721' Perfs at 3230-36'

1st plug pump 60 sx cement to bottom and stop plug at 3100'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 7 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 5 1/2" set at 3729' PBTD 3721' Perfs at 3230-36'

1st plug pumped 60 sx cement to bottom and stopped plug at 3100', 2nd plug squeezed

well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released

8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1985

Maximum pressure 600 psi and shut in 200 psi

1-15-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2522' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed J. H. Metz
(TECHNICIAN)

INVOICED

DATE 1-18-85

INV. NO. 6585