


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Pawnee County. Sec. 35 Twp. 22S Rge. 15W (E) (W)

Location as "NE/CNW&SW" or footage from lines NE NE NE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Barstow Well No. 1
Office Address 1311 Union National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 22 1955
Application for plugging filed December 22 1955
Application for plugging approved December 22 1955
Plugging commenced December 22 1955
Plugging completed December 22 1955
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundridge
Producing formation Depth to top Bottom Total Depth of Well 4075 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8 5/8" set at 221' with 165 sacks cement, 1% gel 4 sacks Calcium Chloride					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled to 250' with heavy mud. Bottom plug at 250' with 1/3 sack Hulls and 20 sacks cement mixed and poured through drill pipe. Hole filled to 35'. Top plug at 35' with 1/3 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.
Address 1311 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr.
1311 Union National Bank Bldg, Wichita
Kansas

SUBSCRIBED AND SWORN to before me this 27th day of December, 1955.

Leta Helm
Notary Public.

My commission expires August 25, 1956

PLUGGING
FILE SEC 35 T 22 R 15 W
BOOK PAGE 26 LINE 42

8-23-55

BARSTOW #1

LOCATION: NE NE NE - Sec. 35,
Twp. 22.S, Rge. 15.W
Pawnee County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
1311 Union National Bank Bldg.,
Wichita, Kansas

SURFACE CASING: 8 5/8" set at 221' with 165 sacks
cement, 1% gel, 4 sacks Calcium Chloride.

OIL STRING: None

ELEVATION: 1988' K. B.
1985' D. F.
1983' G. L.

COMMENCED: December 12, 1955


COMPLETED: December 22, 1955

WELL LOG

0 - 150	Sand & Gravel
150 - 390	Shale
390 - 450	Sand
450 - 500	Shale
500 - 920	Red Bed
920 - 945	Anhydrite
945 - 1800	Shale & Shells
1800 - 1930	Broken Lime
1930 - 2050	Lime
2050 - 2585	Shale & Lime
2585 - 2905	Shale & Shells
2905 - 3355	Shale & Lime
3355 - 3430	Lime
3430 - 3560	Shale & Lime
3560 - 3921	Lime
3921 - 3970	Lime & Chert
3970 - 4010	Shale & Lime
4010 - 4038	Shale & Sand
4038 - 4075	Arbuckle Lime

The Undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Barstow as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.


Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me
this 27th day of December, 1955.


Leta Helm - Notary Public

My commission expires:
August 25, 1956.

PLUGGING
FILE SEC. 35 T. 22 R. 15 W
BOOK PAGE 26 LINE 42

RECEIVED
NOTARY PUBLIC
DEC 29 1955
NOTARY DIVISION
WICHITA, KANSAS