


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 16 Twp. 22 Rge. 34 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Monarch Oil & Gas Company
Lease Name Dralley Well No. A-2
Office Address 1005 Wichita Plaza Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 11-2-67 19____
Application for plugging approved 11-3-67 19____
Plugging commenced 11-17-67 19____
Plugging completed 11-20-67 19____
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well PB3650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	300	None
				5 1/2	None	1829

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

11-27-67

Moved in. Cleaned out cellar. Sanded to 3550'. Dumped 5 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3200' - 3100' and 3000'.

Working pipe. Shot pipe at 2700' - 2500' - 2300' - 2100' - 2000' - 1900' and 1820'. Pulling pipe.

Squeezed well with 10 sacks of mud and 75 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of November, 1967

My commission expires May 27, 1969

Notary Public.

DRILLERS LOGDRALE "A" NO. 2 (WASHDOWN)

COMPANY:	MONARCH OIL & GAS CO.	DESCRIPTION:
CONTRACTOR:	SAGE DRILLING CO.	NE NE NE
COMMENCED:	September 23, 1967	Sec. 16-22-14
		Stafford County, Kansas
COMPLETED:	September 26, 1967	TOTAL DEPTH: 3934'

<u>FROM</u>	<u>TO</u>	<u>REMARKS:</u>
0	3903	Washed down hole to old RTD of 3903'
3903	3934	Drilled 31' of New Hole; Tested; Set 5½" @ 3905' w/140 sax Cement.

I certify that this is a true and correct copy of the operations in the wash down of the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer

Subscribed and sworn to before me this 28th day of September, 1967.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.

NOV 6 1967
CORRELATION DIVISION
WICHITA, KANSAS