


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 16 Twp. 22 Rge. 14 E/W
Location as "NE/CNW/SW" or footage from lines
SE NW NE
Lease Owner Laguna Petroleum Corporation
Lease Name DRALLE Well No. #1
Office Address Suite 370, One Marienfeld Pl. - Midland, TX
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed 3-11 1981
Application for plugging filed 3-11 1981
Application for plugging approved 3-11 1981
Plugging commenced 3-11 1981
Plugging completed 3-11 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug: @ 520' w/40 sacks 50/50 pozmix thru drill pipe

Middle Plug: @ 240' w/30 " " " " " "

Top Plug: @ 40' w/solid bridge of 1/2 sacks hulls & 10 sacks cement
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or (~~owner or operator~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
P.O. Box 823 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1981

My commission expires 4-11-1982

Shirley M. Hogue
Notary Public.

RECORDED
DATE FILED
3-16-81
MAR 16 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: March 5, 1981
 DATE COMPLETED: March 11, 1981

Laguna Petroleum Corp.
 DRALE #1
 SE/4 NW/4 NE/4
 Sec. 16, T22S, R14W
 Stafford County, Ks.

0 - 123' Surface Soil - Sand
 123 - 850' Shale
 850 - 872' Anhydrite
 872 - 3109' Shale & Lime
 3109 - 3356' Lime
 3356 - 3360' Shale
 3360 - 3384' Lime & Shale
 3384 - 3400' Lime
 3400 - 3478' Shale
 3478 - 3650' Lime & Shale
 3650' RTD

ELEVATION: 1949 K.B.

FORMATION DATA

Anhydrite	850'
Topeka	3109'
Heebner	3356'
Toronto	3384'
Douglas	3400'
Lansing K.C.	3478'
RTD	3650'

Surface Pipe: Set new 8-5/8",
 20# pipe at 243' w/200 sacks
 60/40 pozmix, 2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
 statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 12th day of March 1981.

My Comm. Expires:

11-11-1982

Dorothy M. Hague
 Notary Public

MAR 16 1981

CONSERVATION DIVISION
 Wichita, Kansas