

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,756-006

LEASE NAME Miller

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-36

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 23S RGE. 23 (W)

COUNTY Stafford

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506, Russell, KS 67665-0506

PHONE#(303) -825-0120 OPERATORS LICENSE NO. 6111

Date Well Completed 2/23/91

Character of Well D&A

Plugging Commenced 2/23/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/23/91

The plugging proposal was approved on 2-23-91 (date)

by Dick Kapp (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	256'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3900'-522'
50 sks cement @ 522' 15 sks in rathole
50 sks cement @ 280' 10 sks in mousehole
10 sks cement @ 40

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. RECEIVED 750

Address P. O. Box 506, Russell, KS 67665-0506 STATE OF KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: N-B Company, Inc. FFR 28 1991

STATE OF KANSAS COUNTY OF RUSSELL, ss

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 506, Russell, KS 67665-0506

GLENDA R. TIPPIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

15185-2750-0000

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Miller

WELL #1-36

LOCATION: NW SE SW
Section 36-23S-23W
Stafford County, Kansas

LOGGERS TOTAL DEPTH: 3894'

ROTARY TOTAL DEPTH: 3900'

COMMENCED: 2/15/91

CASING: 8-5/8" @ 256' w/175 sks cement

ELEVATION: 1807' K.B.

COMPLETED: 2/23/91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil Shale	160'	Base Kansas City	3606'
Dakota Sand	285'	Marmaton	3625'
Red Bed	315'	Kinderhook	3664'
Anhydrite	494'	Misener	3681'
Red Bed	522'	Viola	3702'
Heebner	3134'	Simpson Sand	3824'
Toronto	3149'	R.T.D.	3900'
Lansing-Kansas City	3314'		

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.



Kyle B. Branum
STATE CORPORATION COMMISSION


Subscribed and sworn to before me on February 26, 1991.

FEB 28 1991

My commission expires: February 6, 1992.

CONSERVATION DIVISION
Wichita, Kansas




Glenda R. Tiffin, Notary Public