

15-185-20273000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely.

Make Required Affidavit

Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County. Sec. 36 Twp. 23 Rge. 11WE/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines \_\_\_\_\_  
150' S of C SE NE  
Lease Owner Stelbar Oil Corporation, Inc.  
Lease Name Volker #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12/26/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 1/16/78 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3705  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	262	none
				5 1/2"	3690	2920

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3665' and ran 5 sacks cement. Loaded hole with salt water, shot pipe at 3027', 2911', pulled 95 joints. Welded on 8-5/8" collar, had hole in surface. Had Till's Well Service run tubing down to 412', Sun pumped in 12 sacks gel. Pulled to 275' and pumped in 100 sacks 50-50 pos with 2% gel.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 27 1978

1-27-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of Jan., 19 78



Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_

5 D7C

DRILLERS LOG

15-185-20273-0000

#1 VOLKER

CASING RECORD:	OPERATOR:	Brunson-Spines	DESCRIPTION:
8 5/8" @ 262' w/ 225 sacks cem.	CONTRACTOR:	Kathol Petroleum, Inc.	150' S. of C. SE NE Sec. 36-23S-11W Stafford Co., Kansas
5 1/2" @ 3690' w/ 100 sacks cem.	COMMENCED:	June 1, 1970	ELEVATION: 1801 K.B.
T.D. 3705'	COMPLETED:	June 9, 1970	
	I.P.		

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>	<u>REMARKS:</u>
surface hole	0	262	
red bed	262	325	
red bed & shale	325	1375	
shale & lime	1374	1745	
lime & shale	1745	2205	
shale & lime	2205	3142	
lime	3142	3380	
lime & shale	3380	3455	
lime	3455	3705	R.T.D.

I hereby certify that the above information is true and correct to the best of my knowledge.

BRUNSON-SPINES

W.S. Brunson

Subscribed and sworn to before me this 15<sup>th</sup> day of June, 1970.

Paul E. Custer  
Notary Public

My Commission Expires:

6-9-1973

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1977

CONSERVATION DIVISION  
Wichita, Kansas