


15-185-12684-0806

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 36 Twp. 23 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C-E/2 NW/4 SW/4
Lease Owner Republic Natural Gas Company
Lease Name O. Volker Well No. 2
Office Address Box 126, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 18 19 45
Application for plugging filed June 30 19 55
Application for plugging approved June 22 19 55
Plugging commenced June 23 19 55
Plugging completed June 27 19 55
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production April 30 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner
Producing formation Viola Depth to top 3703 Bottom 3744 Total Depth of Well 3744 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	336'	None
				7"	3704'	2909'
Viola	Oil	3703	3744			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with sand to 3680'. Dumped 5 sacks cement at 3680'. Pulled casing.
Filled hole with mud to 270'. Made solid with rock and run 25 sacks cement.
Filled hole with mud to 25'. Made solid with rock and run 10 sacks cement to cellar base.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 W. 18th, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
P. B. Horst (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. B. Horst.

Box 126, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 55

Yvonne M. Steensen
Notary Public.

My commission expires 8-20-55

PLUGGING
FILE SEC 26 T 23 R 11W
BOOK PAGE 128 LINE 27

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 - 1955
CONSERVATION DIVISION
Wichita, Kansas

7-1-55

DRILLING LOG

15-185-12684-0000

Company: Republic Natural Gas Company
 Lease and Well: O. Volker #2
 Location: C E/2 NW/4 SW/4 Section 36-23S-11W, Stafford County, Kansas
 Contractor: Gabbert Drilling Company
 Commenced: 10-21-44
 Completed: 1-18-45

0 - 364 Surface hole
 364 - 505 Red bed
 505 - 535 Anhydrite
 535 - 870 Shale & shells
 870 - 1030 Shale & salt
 1030 - 1470 Shale & shells
 1470 - 1660 Lime
 1660 - 1700 Shale & lime
 1700 - 1810 Shale & sand
 1810 - 2185 Lime
 2185 - 2330 Shale
 2330 - 2420 Shale & lime
 2420 - 2435 Shale
 2435 - 2455 Lime & shale
 2455 - 2615 Shale
 2615 - 2760 Shale & shells
 2760 - 2845 Shale & lime
 2845 - 2865 Lime & shale
 2865 - 2970 Lime
 2970 - 3015 Topeka lime
 3015 - 3160 Lime
 3160 - 3240 Shale
 3240 - 3335 Shale & shells
 3335 - 3410 Shale
 3410 - 3430 Lime
 3430 - 3470 K. C. lime
 3470 - 3681 Lime
 3681 - 3698 Shale
 3698 - 3705 Conglomerate
 3705 - 3718 Lime
 3718 - 3724 Lime & dolomite
 3724 - 3744 Lime
 3744 T.D.

Casing Record: 10-3/4" casing cemented at 336' with 250 sacks.
 7" casing cemented at 3704' with 100 sacks.

PLUGGING
 FILE REC 36-23-11W
 DECK FILE 128 LIME 22

RECEIVED
 STATE COMMISSION
 JUN 22 1945
 CONSERVATION DIVISION
 WICHITA, KANSAS