

STATE OF KANSAS
STATE CORPORATION COMMISSION
1 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-22828-00-00

LEASE NAME Daniels

WELL NUMBER 1

4950 Ft. from ^N Section Line

3530 Ft. from E Section Line

SEC. 17 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 5-17-02

Plugging Completed 5-20-02

RECEIVED

MAY 23 2002

5-23-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Globe Operating, Inc.

ADDRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE (620) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 690' | None |
| | | | | 5-1/2" | 3790' | 2000' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3520' and 5 sacks cement. Shot pipe @2400', 2200' and 2000'. Pulled up to 720', pumped 10 sacks gel and 50 sacks cement, pulled up to 300', pumped 50 sacks cement, pulled up to 40' and circulated 20 sacks cement to surface. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed: that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May 2002

[Signature]
Notary Public

My Commission Expires: _____



OR