

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,512-0000

LEASE NAME Alpers

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 22 TWP. 22 SRGE. 12 (E or W)

COUNTY Stafford

LEASE OPERATOR Vac Petroleum Co., Inc.

ADDRESS P. O. Box 780106, Wichita, Ks. 67278

PHONE#(316) 685-0111 OPERATORS LICENSE NO. 04933

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 6-7-90

Plugging Completed 6-8-90 1:30 PM

The plugging proposal was approved on 6-8-90 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top open hole Bottom T.D. 3702

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	280	
				5 1/2	3702	2188.05

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each.

Bottom: 5 sks cement & sand. Top: Pumped 400#s hull, 10 gel, surface pipe leaked. Had to get a rig over hole & run tubing to circulate cement. Hole was bridged off. 6-8-90 drilled out bridge at 40-60' Ran tubing to 900'. Pumped 10 sks gel & 50 sks cement. Pulled tubing to 325' & circulated 100 sks cement to surface. (Cement 60/40 w/6% gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vac Petroleum, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss. 6-22-90

Gary G. Burke

(Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 768, Great Bend, Kansas 67530



AND SWORN TO before me this 21 day of June, 19 90

Lovella L. Mullen
 Notary Public

My Commission Expires 1-13-94