

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County, Sec. 21 Twp. 22 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines ~~XXXXXX~~ NE NE NW  
Lease Owner Hilton Drilling Company, Inc.  
Lease Name Spangenberg Well No. 2  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 4 1953  
Application for plugging filed March 25 1953  
Application for plugging approved March 26 1953  
Plugging commenced April 1 1953  
Plugging completed April 4 1953  
Reason for abandonment of well or producing formation dry hole

NORTH

		0	

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	3691'	2752'
				8-5/8"	225'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from 3610' to 3570' and ran 3 sacks of cement. Cleaned hole and bailed fluid to 225'. Mudded hole to 225', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
I, Henry Peacock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock, Sr.  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of April, 1953

My commission expires April 4, 1956

Margaret Lebitson  
Notary Public.

23-8390-s 6-51-20M  
**PLUGGING**  
FILE SEC 21.22R 124  
BOOK PAGE 87 1953 18

APR 10 1953  
CONSERVATION DIVISION  
Wichita, Kansas  
4-10-53

D R I L L E R ' S L O G

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: NE NE NW  
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Sec. 21-22-12  
 FARM NAME: SPANGENBERG NO. 2 Stafford County  
 Kansas  
 COMMENCED: 2-26-53 ELEVATION: 1866' DF  
 COMPLETED: 3-10-53

Casing Used: 8 5/8 set @ 225' W/150 sacks  
 4 1/2 set @ 3691' W/175 sacks

Sand	100
Sand and Shale	200
Red Bed	660
Anhydrite	685
Shale and Shells	1610
Lime	1890
Sand	1920
Lime, Shale and Sand	1965
Broken Lime and Shale	2125
Broken Lime	2260
Lime and Shale	2860
Broken Lime	2914
Lime	3150
Lime and Shale	3298
Lime	3558
Viola Lime	3597
Chert, Lime and Shale	3626
Shale Lime and Sand	3674
Chert and Lime	3692
Total Depth	3692

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

*Henry Peacock*  
 Henry Peacock, Secretary

Subscribed and sworn to before me this 12th day of March, 1953.

*Margaret Whitman*  
 Notary Public

My commission expires April 4, 1956

