

1 120457

8-13

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,307-0000  
125' S of  
NW NW NE, SEC. 21, T 22 S, R 12 W/E  
4825 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lessee Name Ukens Well # 1

Operator: L.D. Drilling, Inc.

County Stafford 119.89

Name & Address RR 1, Box 183 B

Well Total Depth 3689 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 8 Year: 19 90

Plugging proposal received from L.D. Davis

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: 5 1/2" at 3686' w/150 sx cement, Open hole at 3686-3689'

1st plug sand back to 3636' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hull, and 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6 p.m. Day: 13 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3610' and dumped 5 sx cement on top

of sand through bailer,

2nd plug pumped in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls and 150 sx cement through swedge.

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
8-15-90  
AUG 15 1990

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2788' of 5 1/2" casing. Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (with XXXLXXX) observe this plugging.

DATE: AUG 23 1990

Signed *Steve Durrant* (TECHNICIAN)

INV. NO. 29021