

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21519-00-00  
Spot: CNWSESE Sec/Twnshp/Rge: 21-22S-12W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: SPANGENBERG Well Number: 2  
County: STAFFORD Total Vertical Depth: 4110 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

Conductor Pipe: Size feet: \$133.58  
Surface Casing: Size 8.625 feet: 264 WITH 250 SX CMT  
Production: Size 4.5 feet: 4109 WITH 250 SX CMT  
Liner: Size feet:

Well Type: SWD UIC Docket No: D20753.0 Date/Time to Plug: 09/25/2001 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/25/2001 5:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4033-75'. PUMP DOWN FIBERGLASS 2 3/8" TUBING AT 3925' WITH 25 SX 60/40 POZMIX 6% GEL 3% CC. CEMENT DISPLACED TO 3950'. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 0#. LEFT 2 3/8" FIBERGLASS TUBING FISH FROM 1000' TO 3925'. CASING WAS PARTED AT 1060'. SPOTTED PLUGS THROUGH TUBING. 1ST PLUG AT 710' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1060' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
10-15-2001  
OCT 15 2001  
KCC WICHITA

INVOICED  
DATE 10-15-01  
INV. NO. 2002060806

OCT 02 2001  
MP

Form CP 2/3