

To: 1 120583
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-28
API NUMBER 15- 185-22,074-0000 2512
75' E of
SW SE NE, SEC. 21, T 22 S, R 12 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling, Inc.
Name &

Address RR 1, Box 183 B
Great Bend, KS 67530

2970 feet from S section line

915 feet from E section line

Lease Name Grett Well # 1

County Stafford 121.87

Well Total Depth 3750 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 28 Month: 6 Year: 19 91

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

Remarks: 5 1/2" at 3746' w/125 sx cement, Open hole 3746-3750'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 28 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
7-2-91
JUL 02 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

INVOLCED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 7-18-91

Signed *[Signature]*
(TECHNICIAN)

INV. NO. 32281