

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21428-00-00
Spot: SWNESE Sec/Twnshp/Rge: 21-22S-12W
~~990~~⁶⁵⁰ feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: SPANGENBERG Well Number: 1
County: STAFFORD Total Vertical Depth: 3738 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet: \$121.49
Surface Casing: Size feet: 255
Production: Size 4.5 feet: 3737 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/25/2001 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3640' & 4 SX CMT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 125 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/25/2001 12:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3690-3693'. SANDED TO 3640' & 4 SX CMT WITH DUMP BAILER. PUMPED DOWN 8 5/8" CASING WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 125 SX CMT. MAXIMUM PRESSURE 350#. SHUT IN PRESSURE 300#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2419' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED

OCT 15 2001

10-15-01 KCC WICHITA

INVOICED

DATE 10-15-01
INV. NO. 2002060806

OCT 02 2001

MD

Form 10-275