

1052333

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-21,858-0000
~~SE-SW-NE~~ SEC. 22, T 22 S, R 13 W

9-16-99

STONE MOUNT

CONSERVATION DIVISION - PLUGGING SECTION 4880 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1720 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MATER WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 3865 FEET

OPERATOR: KCC FEE FUND #990076-001 PRODUCTION CSG: SIZE 5 1/2" @ 3864' W/ 160 SX

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8" @ 389' W/ SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE LICENSE NUMBER 31529

ADDRESS PO BOX 467 CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 16 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD LACEY

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 3806-3842

LAY DOWN TUBING. SAND BOTTOM TO 3750'. SPOT 5 SX CEMENT. RECOVER CASING. SPOT 50 SX

CEMENT AT 750', 50 SX CEMENT AT 420', 10 SX CEMENT AT 40'. GEL SPACER IN BETWEEN PLUGS.

RESTORE LOCATION AND TANK BATTERY SITE. PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 16 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED 200# HULLS AND 30 SX COMMON CEMENT DOWN 5 1/2", DISPLACED TO 3100'. MAXIMUM PRESSURE

1300#. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100#

HULLS - 8 5/8" PLUG - 100 SX CEMENT. MAXIMUM PRESSURE 650 PSIG. 450 PSIG SHUT IN PRESSURE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 5 1/2" CASING.

RECEIVED
STATE CORPORATION COMMISSION
9-20-99

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas
FORM CP-2/3

[Handwritten initials and signature]