

1052334

TO: STATE CORPORATION COMMISSION

9-16-99

API NUMBER 15-185-21,903-0000
SE SW NE SEC. 22, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MATER A WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 100

WELL TOTAL DEPTH 4200 FEET

OPERATOR: KCC FEE FUND #990076-002

PRODUCTION CSG: SIZE 5 1/2" @ 4199' W/ 185 SX

NAME AND 130 S MARKET RM 2078

SURFACE CASING: SIZE 8 5/8" @ 385' W/ SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL ~~DE 23-3004~~ SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE LICENSE NUMBER 31529

ADDRESS PO BOX 467 CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 16 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD LACEY

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 3912-4124 5 1/2" SQUEEZED AT 442' WITH 200 SX CEMENT.

UNSEAT PACKER. PULL TUBING. RUN BACK IN HOLE WITH TUBING. SPOT 50 SX CEMENT WITH 200#

HULLS. PULL TUBING TO 750' AND CIRCULATE CEMENT. REMEDIATE LOCATION.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:45 PM DAY: 16 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED DOWN 5 1/2" CASING WITH 400# HULLS - 50 SX CEMENT - 22 SX GEL - 50 SX CEMENT.

MAXIMUM PRESSURE 1600 PSIG. SHUT IN PRESSURE 850 PSIG. PRESSURE TESTED 8 5/8" X 5 1/2"

ANNULUS TO 750 PSIG.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

SEP 20 1999 9-20-99

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3

(Handwritten mark)