

15-185-30399-0001

To: 1121051 7-14
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- Drilled 9/20/63

NE NE NW, SEC. 22, T 22 S, R 13 W/E
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31298Operator: S & S OilName & Address 1128 N. 14th St.Ponca City, OK 74601Lease Name WittWell # 1County Stafford124.18Well Total Depth 3821 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 314Abandoned Oil Well X Gas Well Input Well SMD Well D&A Other well as hereinafter indicated Plugging Contractor Mike's Testing & Salvage Inc.License Number 31529Address P.O. Box 209, Chase, KS 67524Company to plug at: Hour: 10 a.m. Day: 14 Month: 7 Year: 1995Plugging proposal received from Manny Boatright(company name) Mike's Testing & Salvage Inc.(phone) 316-938-2943

core: 4 1/2" at 3821' w/150 sx cement, Perfs at 3426-32, 3442-44, 3558-66, 3558-66, 3586-88,
3688-92, 3742-43, 3774-78'

1st plug sand back to 3375' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 350 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel,
150 lbs. hulls, and 100 sx cement.

Plugging Proposal Received by Duane Rankin

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None Operations Completed: Hour: 11:30 a.m. Day: 14 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3375' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped in 8 5/8" surface casing with 350 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx
gel, 150 lbs. hulls and 100 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi.

5 1/2" collar welded on 8 5/8" surface casing.Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 700' of 4 1/2" casing. RECEIVED

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.Signed Duane Rankin

(TECHNICIAN)

JUL 21 1995

7-21-95

DATE 7-28-95INV. NO. 43192

7-14 NOV 02 1995

FORM CP-2/3
Rev. 01-84