

To: **1 120890**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023
Operator: Kansas Petroleum, Inc.
Name & Address 225 N. Market, Ste. 310
Wichita, KS 67202

API NUMBER 15-185-22,078-0000
100' E of
S/2 NW SW, SEC. 22, T. 22 S, R. 13 W/4
1650 feet from S section line
760 feet from W/4 section line
Lease Name Dunn Well # 1
County Stafford
Well Total Depth 3833 124.57 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 753

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 3 p.m. Day: 4 Month: 2 Year: 19 94

Plugging proposal received from James Tasheff

(company name) Kansas Petroleum, Inc. (phone) 316-267-2266

vers: 5 1/2" at 3832' w/125 sx cement, Perfs at 3793-96, 3606-09, 3442-46'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 4 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3400' with 2 sx cement on top,

2nd plug pumped into 8 5/8" with 300 lbs. hulls, 13 sx gel, 50 sx cement, 7 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-750 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1994

Remarks: Used 60/40 Pozmix 2% gel by Allied. Recovered 1566' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
FEB 11 1994
DATE 39915
WV. NO.

Signed Steve Durrant
(TECHNICIAN)