

8-16

To: 1-120289  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,989-0000

W/2 SW NW, SEC. 24, T 22 S, R 14 W/E

3300 feet from S section line

4950 feet from E section line

Hathaway-Ukens

Lease Name \_\_\_\_\_ Well # 1

County Stafford 125.32

Well Total Depth 3856 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 395

TECHNICIAN'S PLUGGING REPORT

Operator License # 3515

Operator: Sundance Oil & Gas Inc.

Name & Address 500 West 20th

Hutchinson, KS 67502

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nichols Casing Pulling License Number \_\_\_\_\_

Address P.O. Box 108, Geneseo, KS 67444

Company to plug at: Hour: 1:30 p.m. Day: 16 Month: 8 Year: 19 89

Plugging proposal received from George Dauplaise

(company name) Sundance Oil & Gas Inc. (phone) 316-663-6736

were: 5 1/2" at 3855' Perfs at 3798-3800' Elevation 1923' GL

1st plug sand back to 3745' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 16 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3650' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Pumping pressure 0-750 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2475' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED ~~RECEIVED~~ observe this plugging.

DATE 8-24-89 AUG 23 1989 8-23-89

Signed Duane Rankin  
(TECHNICIAN)

INV. NO. 25738  
CONSERVATION DIVISION  
Wichita Kansas