

1052243

TO: STATE CORPORATION COMMISSION

RECEIVED

API NUMBER 15-185-22,121-0000
SW NW SW, SEC. 24, T 22, S, R 14 W

4-8

CONSERVATION DIVISION - PLUGGING SECTION 1650' FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME C & S WELL # 1

7-29-98

TECHNICIAN'S PLUGGING REPORT COUNTY Stafford

OPERATOR LICENSE # 6039 WELL TOTAL DEPTH 3850 125.13 FEET

OPERATOR: L. D. DRILLING, INC. PRODUCTION CSG: SIZE 5 1/2" FEET 3870'

NAME AND ADDRESS R.R. 1 BOX 183-B SURFACE CASING: SIZE 8 5/8" FEET 303'

GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D S & W WELL SERVICING, INC. LICENSE NUMBER 6901

ADDRESS 403 W FRONT, PO BOX 231, CLAFLIN, KS 67525-0231

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 8 MONTH: APRIL YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D S & W WELL SERVICING, INC. (PHONE) 316-587-3361

WERE: PERFORATIONS 3817'-3820' PBTD 3850'

SAND BOTTOM TO 3750' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

PUMP PLUG DOWN 8 5/8" SURFACE PIPE WITH: 300 # COTTENSEED HULLS-10 SX OF GEL-

50 SX OF CEMENT- 10 SX OF GEL- 100# COTTENSEED HULLS- 8 5/8" WIPER PLUG - 100SX OF CEMENT

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD W. LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 2:20 PM DAY: 8 MONTH: APRIL YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3750' AND PLACED 5SX OF CEMENT ON TOP OF SAND.

PUMPED PLUG DOWN 8 5/8" SURFACE PIPE WITH: 300# COTTENSEED HULLS- 10SX OF GEL -

50 SX OF CEMENT- 10 SX OF GEL- 100# OF COTTENSEED HULLS- RELEASED 8 5/8" WIPER PLUG-

100SX OF CEMENT

MAXIMUM PUMP PRESSURE 400 PSIG. INITIAL SHUT IN PRESSURE 150 PSIG

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 1890' OF 5 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (BID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

INVOICED

DATE JUL 22 1998

INV. NO. 50970