

5-6-88

1 120093

API NUMBER 15-185-22,246-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SE, SEC. 21, T 22 S, R 14 W/E

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6581

Lease Name Vice Well # 3-21

Operator: Bison Energy Corporation
Name & Address: Box 782317
Wichita, KS 67278-2317

County Stafford 128.38

Well Total Depth 3950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 6 Month: 5 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3942' Perfs at 3631-35'

1st plug sand back to 3550' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 6 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Pumping pressure 0-400 psi and shut in 100 psi.

5-13-88
MAY 13 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2040' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 5-17-88

INV. NO. 20619