

5-6-88

15.185.00542-0001

To: 1120094  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-24,522

SW NE SW, SEC. 21, T 22 S, R ~~14~~ 15 W/R

1650 feet from S section line

3630 feet from E section line

Lease Name Vice Well # 1A

County Stafford 129.97

Well Total Depth 3999 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 215

TECHNICIAN'S PLUGGING REPORT

Operator License # 6581

Operator: Bison Energy Corporation

Name & Address Box 782317

Wichita, KS 67278-2317

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 6 Month: 5 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3768' Top perms at 3633-37'

1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 6 Month: 5 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5-13-88

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2056' of 5 1/2" casing. MAY 13 1988  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

DATE 5-17-88

INV. NO. 20620