

1050529

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,230-0000

app. 190' SW, SEC. 21, T 22 S, R 14 W/K

C SW 1256 feet from S section line
1256 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6581

Lease Name Vice Well # 2

Operator: Bison Energy Corporation

County Stafford 126.75

Name & Address 16 W. 4th, Suite B

Well Total Depth 3900 (Viola) feet

Hutchinson, KS 67501

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 29 Month: May Year: 19 85

Plugging proposal received from Jim Ray

(company name) DaMac (phone) 316-792-1353

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1948
Anhydrite 876'

1st plug at 900' with 50 sx cement

2nd plug at 330' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:00 pm Day: 29 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement, 2nd plug at 330' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1985 5-31-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

INVOICED

(check date) observe this plugging.

DATE 6-6-85

Signed Richard Lacey
(TECHNICIAN)

INV. NO. 8335

JUL 12 1985 AUG 2 2 1985