

9-26

142R

To: 1 031032  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,609-0000

N/2 SE SE, SEC. 21, T 22 S, R 14 W/E

990 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name Heyen Well # 1-21

Operator: Boger Brothers Drilling, Inc.

County Stafford 128.54

Name & Address P.O. Box 723

Well Total Depth 3955 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling, Inc. License Number 9421

Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 26 Month: 9 Year: 19 89

Plugging proposal received from Ruth

(company name) Boger Brothers Drilling, Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1946' Anhydrite 861'

1st plug at 870' with 50 sx cement,

2nd plug at 450' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 p.m. Day: 26 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement,

9-28-89

2nd plug at 450' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE 10-3-89

Signed Steve Durrant (TECHNICIAN)

INV. NO. 26011

9-26

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 18, 1989  
month day year

N/2 SE.. SE.. Sec 21.. Twp 22S 5, Rg 14.. W East West

OPERATOR: License # 9421  
Name: Boger Brothers Drilling, Inc.  
Address: P. O. Box 723  
City/State/Zip: Great Bend, KS 67530  
Contact Person: Dale Smith  
Phone: 316-792-8151

990 feet from South line of Section  
660 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: Company Tools  
Name: .....

County: Stafford  
Lease Name: Heven Well #: 1-21  
Field Name: Sutton

Well Drilled For: Well Class: Type Equipment:  
X. oil ... Inj ... Infield .X. Mud Rotary  
... Gas ... Storage .X. Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes .X. no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: 1946 est. feet MSL  
Domestic well within 330 feet: ... yes .X. no  
Municipal well within one mile: ... yes .X. no  
Depth to bottom of fresh water: 100  
Depth to bottom of usable water: 200 280  
Surface Pipe by Alternate: ..X 1 ... 2  
Length of Surface Pipe Planned to be set: 310  
Length of Conductor pipe required: None  
Projected Total Depth: A000  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:

If OAWO: old well information as follows:  
Operator: .....  
Well Name: .....  
Comp. Date: ..... Old Total Depth .....

DWR Permit #: .....  
Will Cores be Taken?: ... yes .X. no  
If yes, proposed zone: .....

Directional, Deviated or Horizontal wellbore? ... yes ..X no  
If yes, total depth location: .....

Exp. 3/12/90

Spud 9-2-89 310'


AFFIDAVIT

300' Alt. I Req.

PUSHER Ruth - Smith  
TD 3955' FORMATION 32' into Arb.  
SURFACE PIPE 8 7/8 @ 424  
ANHYDRITE 861 ELEVATION 1946'  
STARTING TIME & DATE 12:00 Noon 9-26-89  
COMPLETION TIME & DATE 1:30 PM 9-26-89  
1st PLUG @ 798' FT. W/ 40 SX  
2nd PLUG @ 870 FT. W/ 50 SX  
3rd PLUG @ 450 FT. W/ 40 SX  
4th PLUG @ 40-0 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15' SX  
MOUSE HOLE CIRCULATED W/ 200 SX  
WATER WELL PLUGGED W/ To landowner 7-8 Cement SX

CEMENT COMPANY Halliburton  
TECHNICIAN DG  
TYPE OF CEMENT 60/40 Poz 60/4

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas



Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.