

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21665-00-00
Spot: E2NESWNE Sec/Twnshp/Rge: 22-12S-21W
3594; 3630 feet from S Section Line, 1600 feet from E Section Line
Lease Name: KING 1658 Well #: 7
County: TREGO Total Vertical Depth: 3971 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3951		125 sx
SURF	8.625	260		170 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2017 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3410

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls and 1100 # gel.
Port Collar at 2177' w/550 sx cement.
Perforations: 3925' - 3937'.
Fish in hole at 2520'. Plug at 2520' per district supervisor.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2017 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

01/22/2017 - Ran tubing to 2520' and pumped 75 sx cement. Pulled tubing to 1600' and pumped 60 sx cement w/150 # hulls. Pulled tubing to 800' and pumped 75 sx cement w/200 # hulls. Lost circulation. Pulled tubing out.

01/24/2017 - Tagged cement at 562' and pumped 75 sx cement w/150 # hulls. Pulled tubing. Topped off with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 400 psi.

GPS: 38.99636 -099.63709


Remarks: QUALITY WELL SERVICE TICKET # 6129 ANGLE FEE FUND PROJECT CONTROL # 20170006-006
006

Plugged through: TBG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed



(TECHNICIAN)

CM

FEB 7 1 2017

MAR 13 2017

CONSERVATION DIVISION
WICHITA, KS

3-13-17