

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-00615-00-00
Spot: NESWSE Sec/Twnshp/Rge: 18-10S-25W
1006 feet from S Section Line, 1659 feet from E Section Line
Lease Name: KRUG A Well #: 1
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4029		
SURF	8.625	163		100 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2017 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3410

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement, 1300 # gel and 800 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2017 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 2210', 1350' and 150'. Ran tubing to 3125'. Hit something hard. Pulled up one joint and pumped 90 sx cement w/100 # hulls. Pulled tubing to 2225' and pumped 90 sx cement w/100 # hulls. Pulled tubing to 1360' and pumped 200 sx cement w/300 # hulls. Well started to circulate w/120 sx cement. Pulled tubing to 180' and pumped 45 sx cement. Circulated cement to pit. Had cement flag. POOH. Hooked to casing and pumped 45 sx cement at 300 - 325 psi. Hole in surface pipe. Filled with 5 sx cement.

GPS: 39.17818 -100.15120

KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6131 KRUG FEE FUND PROJECT CONTROL # 2014003-001

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

FEB 16 2017