

1 080600

FEB 18 1987  
F 1 2 7

15-145.00190-0001

API NUMBER 15- N/A

NW NW NW, SEC. 35, T 22 S, R 15 W/E

4950 feet from S section line

4950 feet from E section line

Lease Name Lovett Well # 1

County Pawnee 124.44

Well Total Depth 3829 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 390

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5654

Operator: Rine Drilling Company  
Name & Address 300 West Douglas, Suite 600  
Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 18 Month: 2 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3829' Perfs at 3682-90' Elevation 1986' GL

1st plug sand back to 3630' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, and 125 sx cement.

Plugging Proposal Received by Richard Lacey & Bud Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 18 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3630' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 450 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2480' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

2-25-87

FEB 25 1987

CONSERVATION DIVISION  
Wichita Kansas

**INVOICED**  
(If additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE 2-26-87

INV. NO. 16235

Signed J. R. Metz  
(TECHNICIAN)