

To: 1 120708 5-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-25,102 15-185-01023-0002
NE NE NW, SEC. 33, T. 23 S, R. 11 W/E
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # none

Lease Name Stalcup Well # 1

Operator: Doug Holtz

County Stafford

Name & Address 30 W. 14th

Well Total Depth 3784 122.98 feet

Hutchinson KS 67501

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well

ENHP Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 7 Month: 5 Year: 19 92

Plugging proposal received from Rick Davis

(company name) Pipe Recovery Inc. (phone) 316-793-3922

logs: 5 1/2" at 3615' w/100 sx cement, PBTD 3615', Perfs at 3446-48, 3552-58'

1st plug sand back to 2950' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 7 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 2950' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

2 3/8" tubing at 3000'.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 6-3-92

Signed Duane Rankin (TECHNICIAN)

INV. NO. 35364

5-11-92
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
MAY 11 1992