

To: 1090014
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-16 15-083.10293-0000
API NUMBER 15-Drill Completion Date 2/21/63

C SE SW, SEC. 16, T 22 S, R 22 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5363
Operator: Berexco, Inc.
Name & Address Box 723.
Hays, KS 67601

Lease Name Ray Lee Well # 7
County Hodgeman 145.60
Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4469' with 100 sx cement

1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 240 sx cement down 5 1/2"

3rd plug pump 120 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 16 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 240 sx cement down 5 1/2" casing, Maximum pressure 900 psi and shut in 350 psi.

3rd plug pumped 120 sx cement down 8 5/8" annulus, Maximum pressure 550 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1990 10-19-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form, Kansas
Conservation Division, Wichita, Kansas)

INVOICED (if necessary) observe this plugging.

DATE 10-26-90

BIV. NO. 29743

Signed [Signature]
(TECHNICIAN)