

To: 1 090015
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
230 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-16 15-083-10288-0000
API NUMBER 19 - Drill Completion Date 12/20/62

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco, Inc.
Name &
Address Box 723
Hays, KS 67601

C SE SE, SEC. 16, T 22 S, R 22 W/E
660 feet from S section line
660 feet from E section line

Lease Name Ray Lee Well # 2

County Hodgeman 144.13

Well Total Depth 4435 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:10 a.m. Day: 16 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4433' w/100 sx cement, Open hole

1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 240 sx cement down 5 1/2",

3rd plug pump 120 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped 240 sx cement down 5 1/2" casing. Maximum pressure 400 psi and shut in 200 psi.

3rd plug pumped 120 sx cement down 8 5/8" annulus. Maximum pressure 450 psi and shut in 150 psi.

OCT 19 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-26-90

INV. NO. 29742

Signed [Signature]
(TECHNICIAN)