

1 090575

8-25

15.083-16289.0000

STATE CORPORATION COMMISSION
Wichita State-Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 10/28/62

C NW SE, SEC. 16, T 22 S, R 22 W/EX

1980 feet from S section line

1980 feet from E section line

Lease Name Ray Lee Well # 3

County Hodgeman 144.89

Well Total Depth 4458 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor BEREXCO INC. License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 8 Year: 19 95

Plugging proposal received from Bob Grant

(company name) BEREXCO INC. (phone) 913-628-6101

logs: 5 1/2" at 4454' w/100 sx cement, Open hole 4454-58'

1st plug run tubing to bottom, circulate cement to Anhydrite,

2nd plug perforate at 600', circulate cement to surface,

Check backside.

8-29-95

Plugging Proposal Received by Steve Durdant

RECEIVED
STATE CORPORATION COMMISSION

(TECHNICIAN) 1995

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 25 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4449', filled with 254 sx cement & 2 sx hulls to 640',

2nd plug pulled tubing out of hole. Perforated casing at 600'. Ran tubing to 200' with

packer. Tried to pump into at 500#. Instant pressure. Pulled packer out of the hole. Ran tubing to 600' and circulated cement to surface with 50 sx,

3rd plug pumped 12 sx cement down backside.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed: [Signature] (TECHNICIAN)

DATE SEP 01 1995

INV. NO. 43396