

1052374

TO: STATE CORPORATION COMMISSION

API NUMBER 15-083-10,287-0000  
C SW SE SEC. 16, T 22 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME RAY LEE WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 144.66

OPERATOR LICENSE # 5363

WELL TOTAL DEPTH 4451 FEET

OPERATOR: BEREXCO, INC

PRODUCTION CSG: SIZE 5 1/2" @ 4441' WITH 200 SX

NAME AND BOX 723

SURFACE CASING: SIZE 9 5/8" @ 261' WITH 200 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 25 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MARK LEIKER

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: OPEN HOLE AT 4441-4451 SQUEEZED 3555 W/100 SX. 3671-88 W/245 SX, 3000-3070 W/65 SX 3800-19 W/245 SX.

RAN TUBING TO 4400'. SPOTTED 200# HULLS AND 50 SX COMMON CEMENT. PULLED TUBING TO 1600'

SPOTTED 25 SX CEMENT. PERFORATED 5 1/2" CASING AT 600'. RAN TUBING TO 600' AND CIRCULATED 5 1/2"

FULL OF CEMENT WITH 55 SX OF 60/40 POZ 6% GEL. PULLED TUBING. PUMPED DOWN 5 1/2" CASING WITH

70 SX 60/40 POZ 6% GEL. MAXIMUM PRESSURE 600 PSIG. SHUT IN WITH 500 PSIG. PUMPED DOWN 9 5/8" X

5 1/2" ANNULUS WITH 70 SX 60/40 POZ 6% GEL. MAXIMUM PRESSURE 600 PSI. SHUT IN WITH 400 PSI.

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 12:35 PM DAY: 25 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT RAN TUBING TO 4440' SPOTTED 200# HULLS & 50 SX COMMON CEMENT.

PULLED TUBING TO 1600' SPOTTED 25 SX CEMENT. PERFORATED 5 1/2" CASING @ 600'. RAN TUBING TO

600' & CIRCULATED 5 1/2" FULL OF CEMENT W/55 SX 60/40 POZ 6% GEL. PULLED TUBING. PUMPED DOWN

5 1/2" CASING WITH 70 SX 60/40 POZ 6% GEL. MAXIMUM PRESSURE 600 PSIG. SHUT IN W/500 PSIG.

PUMPED DOWN 9 5/8" X 5 1/2" ANNULUS WITH 70 SX 60/40 POZ 6% GEL. MAXIMUM PRESSURE 600 PSIG.

SHUT IN PRESSURE 400 PSIG.

STATE CORPORATION COMMISSION  
2-28-00

REMARKS: USED 60/40 POZ MIX 6% GEL & COMMON CEMENT BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard M. Jacey  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3

**INVOICED**  
DATE 2/28/00  
INV. NO. 061304

FEB 28 2000