

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cheyenne Exploration Inc.

Complete Address 357 Lulu Office Center Wichita, Ks

Lease Name Morton (Smith Well No. 1 QWVO

Location SW/SW/SE Sec. 15 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3731

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 11:00 AM Day 3 Month 8 Year 1971

The above well was plugged as follows:

269 ft 8 5/8 surface pipe cement circulated. 3730 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 3584 ft. Sand back to 3550 ft,
5 sacks cement with bailer. Pulled 2320 ft 5 1/2. Pump 3 sacks hulls,
20 sacks gel., 100 sacks cement to surface.

Pumped by Dowell Chemical Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell Biberstein
Well Plugging Supervisor

DATE 8/16/71
INV. NO. 4104-11