

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 08 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company

Complete Address Box 287. Great Bend, Kansas 67530

Lease Name Barstow (SWD) Well No. D-1

Location NE SW NW Sec. 32 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4210'

Abandoned Oil Well        Gas Well        Input Well        SWD Well XX D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12 N Day 5 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 4210' 8 5/8 csg set 365' cwc 200 sk.

4 1/2 csg set 4016' cw 200 sk cmt.

Squeezed anulus with 75 sk gel & water & 75 sk poz cem. No pipe recovered.

Pressured anulus(600 lbs)

Pumped down 4 1/2 csg with 100 sk 60-40 poz W/400 lbs hulls -23 sk gel & water -

released plug & pumped 38 sk 60-40 poz by HOWCO. PP 600 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Wosney  
Well Plugging Supervisor

DATE 9-9-75

INV. NO. 1883-W