

N
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Et Al, Inc.

Complete Address 119 Cameran Bldg., 2915 Classen Blvd. Oklahoma City, Okla. 73106

Lease Name Guffey Well No. 1

Location SW SW SW Sec. 34 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3126

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 5 P Day 8 Month 11 Year 1974

The above well was plugged as follows:

- Total Depth 3126° 9 5/8 csg set at 645° cwc
- 4 1/2 csg set at 3124° cw 300 sk cmt. Top perf. (2969)
- Filled 4 1/2 csg with sand (3126-2950) dumped 3 sk cmt W/dump bailer. (2950-2920)
- Cutoff & recovered 1850° of 4 1/2 csg.
- Pumped down 9 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug &
- pumped 130 sk 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11/13/74
INV. NO. 289-W