

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1965

4-30-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kans

Lease Name Orinda Well No. 1

Location SW SW SW Sec. 34 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4053

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kans License No. 456

Operation Completed: Hour 7:30PM Day 27 Month 4 Year 65

The Above well was plugged as follows:

9 5/8" 648' circulated with cement - 7" 4053' with 90 sax cement
PB to 4016' perforated at 3554'

Set plug at 3525' sand and 5 sax cement set with dump bailer - pulled
2878' 7" to 620', circulated hole with heavy gel mud through 7" - displaced
25 sax cement through 7" at 450', heavy mud to 180', displaced 25 sax
cement through 7" at 180', heavy mud to 30', set 10 sax cement to bottom
cellar.

Mudding and cementing by Knight Casing Pulling Pump Truck.

I hereby certify that the above well was plugged as herein stated.

NOTICE

DATE 4/30/65 Signed: Edson Petty
INV. NO. 1081-65 Well Plugging Supervisor