

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1967  
3-6-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name D. J. Iannitti

Complete Address: Box 387 Hosington, Kansas

Lease Name Barstow "A" Well No. 1

Location SE NW NW Sec. 32 Twp. 22 Rge. 15 (E) (W) X

County Pawnee Total Depth 4024

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 3 P Day 1 Month 3 Year 1967

The Above well was plugged as follows:

Total Depth 4024' 8 5/8 csg set at 225' cwc 150 sc.

5 1/2 csg set at 4024' cw 100 sc cement.

PB 3790' Top perf. 3546'

Filled with sand to 3530' and dumped 5 sc cement with dump bailer.

Recov. 2950' of 5 1/2 csg.

Rumped thru 8 5/8 plug container with 40 sc gel mud and 85 sc, cement. Shut-in-No Pres.

Run wire line- Top of f cement 75'

Filled with mud to 15' set plug and 5 sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/7/67  
INV. NO. 4859-W

Signed: [Signature]  
Well Plugging Supervisor