

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 July 2014 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 33790 Name: Beymer Bros dba Beymer & Beymer Address 1: 222 N Main Street Address 2: PO Box 363 City: Lakin State: KS Zip: 67860 + 0363 Contact Person: Robert Beymer Phone: (620) 355-6232 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Chase Depth to Top: 2561 Bottom: 2580 T.D. 2720

API No. 15 - 093-00633-0000 Spot Description: SW SW NE Sec. 35 Twp. 22 S. R. 37 East West 2,665 Feet from North South Line of Section 2,327 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Kearny Lease Name: Davis Well #: 1 Date Well Completed: 1953 The plugging proposal was approved on: 2/22/17 (Date) by: Ken Jehlik (KCC District Agent's Name) Plugging Commenced: 3/1/2017 Plugging Completed: 3/1/2017

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Chase Gas Surface 8 5/8 770 0 and Chase Gas Production 5 1/2 2700 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP c/o 2100' w 2sf cmt No casing recovered. CIBP c/o 925' Test csg to 800#. Holding. Perforate 3 holes c/o 900', Injection rate 4 BPM c/o 100psi down casing 5 1/2" csg. Mix and pump 230 sf cement via 5 1/2" csg and the 5 1/2 x 8 5/8 annulus full of cement. Had full returns. Hold stayed full.

KCC WICHITA MAR 08 2017 RECEIVED 3-8-2017

Plugging Contractor License #: 33961 Name: Consolidated Address 1: Address 2: City: Oakley State: KS Zip: Phone: (785) 627-8822

Name of Party Responsible for Plugging Fees: Beymer & Beymer State of Kansas County, Kearny, ss. Robert K Beymer (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert K Beymer