

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 9 TWP. 22S RGE. 14W ~~NW~~
Location as in quarters or footage from lines:

NW SE NE

Lease Owner F. G. Holl
 Lease Name Freeda Dralle Well No. 1-9
 Office Address 6427 East Kellogg, Wichita, Kansas 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed June 6, 1983
 Application for plugging filed June 5, 1983
 Plugging commenced 11:45 PM, June 5, 1983
 Plugging completed 2:15 AM, June 6, 1983
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Carbutton

Producing formation _____ Depth to top _____ bottom T.D. 3960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	293'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Mud plugged through open ended drill pipe,
50 sacks at 870'; 40 sacks at 330'; 1/2 sack hulls,
plug and 10 sacks at 40'; 15 sacks in rathole with
joint of pipe. Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) F. A. Wuellner
F. A. Wuellner, Secretary
 (Address)
P. O. Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 7th day of June, 1983.

My Commission expires:



Agnes D. Wurst
 Agnes D. Wurst, Notary Public

STATE CORPORATION COMMISSION

JUN 16 1983

CONSERVATION DIVISION
Wichita, Kansas

6-16-83

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- FREEDA DRALLE #1-9

Located: NW SE NE, Section 9-22S-14W, Stafford County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 31, 1983

COMPLETED: June 6, 1983

TOTAL DEPTH: 3960'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 130	Surface Soil and Sand	Ran 7 joints new 8 5/8", 24# casing. 281.23' pipe set at 293' K.B.
130 - 156	Clay	Cemented with 240 sacks 60/40 Pozmix plus 3% cc. Plug down at 6:15 PM, 5-31-83 by Howco.
156 - 296	Clay and Shale	
296 - 770	Shale and Lime Stringers	
770 - 3885	Lime and Shale	
3885 - 3960	Arbuckle	Plugged.

Deviation Surveys: 3/4° at 2128'
3/4° at 3655'

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1983

CONSERVATION DIVISION
Wichita, Kansas