


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 7 Twp. 22S Rge. 14W(E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW3/4" or footage from lines NE SE SE

Lease Owner Imperial Oil Company

Lease Name STANDISH Well No. 1

Office Address 780 Fourth Natl. Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 11/2/62 19

Application for plugging filed 11/2/62 19

Application for plugging approved 11/2/62 19

Plugging commenced 11/2/62 19

Plugging completed 11/2/62 19

Reason for abandonment of well or producing formation

No commercial quantities of oil found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation Depth to top Bottom Total Depth of Well 3960 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing	8-5/8"	at 315'	not pulled		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 250' with 20 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1962

CONSERVATION DIVISION
Wichita, Kansas

11-26-62

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
(If additional description is necessary, use BACK of this sheet)

Address Box 97, WaKeeney, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
John Lehman (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman
780 Fourth Natl. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 62

My commission expires July 5, 1966

Bette J. Silcott
Notary Public.

DRILLER'S LOG

STATE COMMISSION
 NOV 23 1962
 CONSERVATION DIVISION
 Wichita, Kansas

Imperial Oil Company
 780 Fourth National Building
 Wichita, Kansas

STANDISH NO.: 1
 NE SE SE 7-22S-14W
 Stafford County, Kansas

Total Depth: 3960'

Commenced: 10/23/62 Completed: 11/1/62

Elevation: 1962 K.B.
 Production: Dry

Contractor: Imperial Oil of Kansas, Inc.
 Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 315' with 225 sacks cement

Figures indicate bottom of formations:

		<u>TOPS</u>		
Shale & Sand	885'	Heebner	3365	(-1405)
Anhydrite	922'	Toronto	3389	(-1427)
Red Bed & Shale	1130'	Brown Lime	3487	(-1525)
Shale & Shells	2040'	Lansing	3496	(-1534)
Shale & Lime	2405'	Base Kansas City	3723	(-1761)
Shale & Shells	2930'	Conglomerate Chert	3803	(-1843)
Shale & Lime	3312'	Viola	3833	(-1871)
Lime	3400'	Simpson Shale	3863	(-1901)
Shale & Lime	3520'	Arbuckle	3932	(-1970)
Lime	3804'	R.T.D.	3960	(-1998)
Lime & Chert	3850'			
Lime	3960'			

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

Raymond R. Dombaugh
 Raymond R. Dombaugh

Subscribed and sworn to before me this 19th day of November, 1962.

My commission expires:

July 5, 1966

Bette J. Silcott
 Bette J. Silcott, Notary Public