

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD

County, Sec. 7 Twp. 22S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Sundermeier Well No. 1
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 23, 1963 19
Application for plugging filed July 23, 1963 19
Application for plugging approved July 23, 1963 19
Plugging commenced July 23, 1963 19
Plugging completed July 23, 1963 19
Reason for abandonment of well or producing formation non-productive

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3924 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	295'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from 3924 feet to 240 feet, plug of hulls and wood and 20 sacks through drill pipe; mud to 40 feet another plug and 10 sacks and 2 sacks in rat hole - job completed at 6:00 P. M.

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1963
7-29-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor QUAKER DRILLING CO., INC.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 1963

My commission expires August 10, 1965

Virginia M. Woodell
Notary Public.



WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Contractor: Quaker Drilling Co., Inc.

No. 1 Sundermeier
SE SW NW Sec. 7-22S-14W
Stafford County, Kansas

Commenced: July 12, 1963

Completed: July 23, 1963

Elevation: 1962 K.B.

Production: D & A

Casing Record

Set 8 5/8 " Casing at 295 feet with 275 sacks cement

(Figures Indicate the Bottom of the Formations)


<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	245	Heebner	3370 -1384
Shale	295	Brown Lime	3467 -1505
Red Bed and Shale	347	Lansing	3477 -1515
Sand	415	Base of Kansas	
Shale and Red Bed	889	City	3707 -1745
Anhydrite	918	Viola	3764 -1802
Shale and Shells	1620	Simpson	3822 -1860
Lime and Shale	3085	Arbuckle	3883 -1921
Lime	3160	Rotary Total	
Lime and Shale	3285	Depth	3925 -1963
Lime	3455		
Lime and Shale	3540		
Lime	3780		
Lime and Chert	3824		
Cherty Lime & Shale	3860		
Cherty Lime	3925		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SW NW of Section 7, Township 22 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: 

SUBSCRIBED AND SWORN TO before me a Notary Public this 26th day of July, 1963.


Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1965

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION
Wichita, Kansas