


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 22 Rge. 13 (E) (W)X
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Morgenstern & Specter
Lease Name Dora Hahn Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 11-22-52 19
Application for plugging filed September 15, 1956 19
Application for plugging approved September 17, 1956 19
Plugging commenced September 18, 1956 19
Plugging completed September 28, 1956 19
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production July, 1956 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Brundage
Producing formation Arbuckle Depth to top 3836' Bottom 3836' Total Depth of Well 3837' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			8 5/8"	278'		None
			5 1/2"	3837'		2787.66'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand to 3555'. Dump 5 sacks cement fill hole with mud to 230', put in rock bridge, dump 20 sacks cement. Mud to 35' rock bridge and 10 sacks cement to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Co.
Address Heisington, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur Morgenstern
Box 661 - Russell -
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of Oct., 1956

My commission expires April 14, 56

A. J. [Signature]
Notary Public.

STATE CORPORATION
OCT 15 1956

CONSERVATION DIVISION
Wichita, Kansas

10-5-56

PLUGGING
FILE SEC. 21 Twp. 22 Rge. 13
BOOK PAGE 99 Vol. 22

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-185-00227-0000

Company- SUNRAY OIL CORPORATION
Farm- Hahn No. 1

SEC. 21 T. 22 R. 13W
SW SW NE

Total Depth. 3839
Comm. 11-6-52 Comp. 11-22-52
Shot or Treated.
Contractor. Mouser Drilling Co.
Issued. 3-14-53

County Stafford
KANSAS



Elevation. 1904

Production. Phys. 16 B0, no wtr

Figures indicate Bottom of Formations.

cellar	5
sand	100
sand & shale	160
sand	220
shale	295
shale & shells	845
red bed & shale	1200
salt	1235
shale & shells	1555
shale & lime	2250
lime	2375
lime & shale	2980
lime	3275
shale & lime	3410
lime	3705
cherty conglomerate	3720
lime & chert	3745
chert	3779
lime & shale	3805
shale	3825
shale & lime	3836
Arbuckle	3839
Total Depth	

TOPS:	
Topeka	2890
Heebner	3278
Toronto	3298
Brown lime	3406
Lansing	3430
Base KC	3659
Marmaton	3668
Congl. Chert,	3710
Viola	3733
Simpson shale	3776
Simpson sand	3794
Arbuckle	3836

RECEIVED
STATE CORPORATION
SEP 17 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 21 T. 22 R. 13W
BOOK PAGE 99 LINE 22