

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Stafford County. Sec. 22 Twp. 22 Rge. 13 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NW SW NE
Lease Owner E. L. Schonhoff
Lease Name Mater Well No. 2
Office Address 2823 Paseo, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 2-73 _____ 19____
Application for plugging approved 2-73 _____ 19____
Plugging commenced 2-28-73 _____ 19____
Plugging completed 3-2-73 _____ 19____
Reason for abandonment of well or producing formation _____

		X	

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	353	None
				5 1/2"	3870	2848

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2-28-73 Plug off bottom - dump sand to 3850', mix and dump 5 sacks cement.

3-2-73 Plug off top. Set 10' Rock Bridge @ 250', fill 8-5/8" surface casing from 250' to base of cellar with 3000# PSI Ready Mix Concrete.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1973
CONSERVATION DIVISION
Wichita, Kansas
4-17-73


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
E. L. Schonhoff (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) E. L. Schonhoff
2823 PASEO GREAT BEND KS
(Address)

Subscribed and Sworn to before me this 16th day of April, 1973



Mary Sue Zagala
Notary Public.

WELL LOG

15-185-19359-0000

COMPANY Phillips Petroleum Company

SEC. 22 T. 22S R. 13W

FARM Mater

NO. 2

LOC. NW SW NE


TOTAL DEPTH 3873'

COUNTY Stafford

COMM. 10-8-63

COMP. 10-17-63

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 353' w/220 SX

5 1/2" @ 3870' w/75 SX

ELEVATION 1894' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 95' Surface Sand
- 260' Sand and Shale
- 750' Red Bed
- 775' Anhydrite
- 1545' Red Bed and Shale
- 1800' Shale and Lime
- 2185' Lime
- 2565' Limey Shale
- 2800' Shale w/Lime Streaks
- 2965' Lime and Shale
- 3080' Limey Shale
- 3180' Lime and Shale
- 3241' Lime
- 3395' Shale and Lime
- 3455' Lime and Shale
- 3690' Lime
- 3756' Viola
- 3810' Simpson Shale
- 3812' Lime
- 3873' Arbuckle
- 3873' RTD

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1973
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Mater #2 well.

Sam N. Stephens

Subscribed and sworn to before me this 22nd day of October 19 63

My Commission Expires: April 14th, 1967

Arthur J. Wilde
NOTARY PUBLIC