


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 7 Twp. 22S Rge. 14W ~~EXX~~
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
S/2 SE/4 NW/4

Lease Owner Icer Addis
Lease Name Sundermeier Well No. 1
Office Address 5307 E. Central, Wichita, KS 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed 2-3 1979
Application for plugging filed 2-3 1979
Application for plugging approved 2-3 1979
Plugging commenced 2-3 1979
Plugging completed 2-3 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens - Pratt, KS
Producing formation Depth to top Bottom Total Depth of Well 3910
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows:

Filled hole w/mud, spotted 50 sx of 50/50 pozmix thru open end D.P. @ 480', mud to 40', 1/2 sx hulls & wood plug for solid bridge, pumped 12 sx to base of cellar, 3 sx in rathole, completed @ 2:30 a.m. 2-3-79 by Halliburton;

Witness: Bill Owens - St. Pluggger - Pratt, Kansas
Gary Bagby - Sterling, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB - 7 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

CONSERVATION DIVISION
Wichita, Kansas

2-7-79

STATE OF Kansas COUNTY OF Sedgwick, ss.


John S. Crowe (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Building, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 79

[Signature]
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

February 3, 1979

WELL LOG- - - - -Sundermeier #1

Location: S/2 SE/4 NW/4 of Sec. 7-22S-14W
Stafford County, Kansas.

OWNER: Icer Addis
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: January 27, 1979
COMPLETED: February 3, 1979

Rotary Total Depth: 3910'

LOG

CASING RECORD

0 - 503	Soil, sand & shale-red bed
503 - 889	Shale & sand
889 - 939	Anhydrite
939 - 1750	Shale & shells
1750 - 3528	Shale & lime
3528 - 3565	Lime
3565 - 3650	Lime & Shale
3650 - 3680	Lime
3680 - 3910	Lime & shale

Ran 12 jts. 8-5/8", 28#, 8Rd, Rge 3
used csg. - tallied 491' set @ 498
KB w/300 sx 50/50 pozmix 2% gel
3% cc - circulated - plug down @
2:30 a.m. 1-28-79 by Halliburton.

Plugged 2:30 a.m. February 3, 1979

RECEIVED
STATE CORPORATION COMMISSION

FEB - 7 1979

CONSERVATION DIVISION
Wichita, Kansas