


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 7 Twp. 22S Rge. 14 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C N/2 S/2 SW
Lease Owner Gear Petroleum Co., Inc.
Lease Name KIRKMAN Well No. 1
Office Address 300 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed March 7 19 81
Application for plugging filed March 7 19 81
Application for plugging approved March 7 19 81
Plugging commenced March 7 19 81
Plugging completed March 7 19 81
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	553'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 588' w/50 sacks 50/50 Pozmix, 4% Gel
2nd plug @ 40' w/bridge & 10 sacks 50/50 Pozmix, 4% Gel
10 sacks cement in rat hole

RECEIVED
MAR 13 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
Milford Martin (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 1425, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 81

BEVERLY SHEWBART
Notary Public
Barton County, Kansas
My Appt. Exp. APR 14, 1982

[Signature] Notary Public.

My commission expires

DRILLERS' WELL LOG

DATE COMMENCED: February 28, 1981
 DATE COMPLETED: March 7, 1981

Gear Petroleum Co., Inc.
 "KIRKMAN # 1"
 C N/2 S/2 SW
 Sec 7-T22S-R14W
 Stafford County, Kansas

0 - 230' Surface Clay, Sand
 230 - 350' Blue Shale, Red Bed
 350 - 570' Sand, Red Bed
 570 - 1086' Shale
 1086 - 1840' Shale, Lime
 1840 - 3488' Lime, Shale
 3488 - 3712' Lime
 3712 - 3771' Lime, Shale
 3771 - 3782' Lime, Shale, Sand, Chert
 3782 - 3902' Lime
 3902 - 3920' Dolomite
 3920' RTD

API # 15-185-21,238

ELEVATION: 1965 K.B.

FORMATION TOPS (log)

Heebner	3356	-1391
Brown Lime	3479	-1514
Lansing	3488	-1523
Base K.C.	3712	-1747
Cong.	3771	-1806
Viola	3782	-1817
Arbuckle	3902	-1937
LTD	3908	-1943
RTD	3920	-1955

SURFACE PIPE:

Set new 8 5/8", 20# pipe at
 553' w/375 sacks Common,
 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss

RECEIVED
 MAR 13 1981
 CONSERVATION DIVISION
 Wichita, Kansas

I, Milford Martin, of Mustang Drilling & Exploration, Inc. do state
 that the above is true and correct to the best of my knowledge.


Milford Martin

 Milford Martin

Subscribed and sworn to before me this 12th day of March, 1981.

Beverly Shewbart

 Notary Public

 BEVERLY SHEWBART
 Barton County, Kansas
 My App. Exp. 14, 1982

My Appointment Expires