

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 21 Twp. 22 Rge. 13 (E) (W) X

Location as "NE/CNW/SE/SW" or footage from lines SE/SE/NW

Lease Owner E. K. Edmiston

Lease Name Dudrey

Office Address Box 1094 Great Bend, Kansas 67530 Well No. 1

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 10-28-71 19

Application for plugging approved 19

Plugging commenced 11-4-71 19

Plugging completed 11-9-71 19

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 3839 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250	None
				5 1/2"	3837	2841.27'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed a plug to 3540'. Dumped sand to 3500' and 5 sacks of cement. Shot pipe at 3164' with 23" tension on 3000 psi. Shot at 3031 and had 25" tension at 3000 psi. Shot at 2805, 2623, 2511, 2316, 2213, 2005, and 1816 ft. Worked pipe loose. Laid down a total of 60 jts. of 5 1/2" casing. Cut casing head, welded on 8 5/8" collar. Squeezed well with 2 sacks hulls, 15 sacks gel and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1971
CONSERVATION DIVISION
Wichita, Kansas


11-24-71

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698 Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 22nd day of November, 1971



Cathy Miller
Cathy Miller Notary Public.

My commission expires September 30, 1975

Jim Rockwell

DRILLER'S LOG

COMPANY: E. K. EDMISTON
 801 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

ROTARY DRILLING COMMENCED: DECEMBER 9, 1962

ROTARY DRILLING COMPLETED: DECEMBER 19, 1962

WELL NAME: DUDREY NO. 1
 SE SE NW SEC. 21-22S-13W
 STAFFORD COUNTY, KANSAS

CONTRACTOR: E. K. EDMISTON DRILLING CO., INC.
 501 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

CASING RECORD: 8 5/8" @ 250' w/ 250 sacks cement
 LOG *5 1/2 3837 - 600 gal Latex Cement Dec 1962*

0 - 210	Sand and Shale
210 - 256	Shale and Shells
256 - 380	Shale
380 - 765	Red Bed, Shale and Shells
765 - 797	Anhydrite
797 - 835	Shale and Shells
835 - 1290	Shale and Shells
1290 - 1592	Shale
1592 - 1820	Shale and Lime
1820 - 2130	Lime
2130 - 2335	Shale and Lime
2335 - 2915	Shale and Lime
2915 - 3165	Lime and Shale
3165 - 3270	Lime
3270 - 3330	Lime
3330 - 3425	Lime and Shale
3425 - 3504	Lime
3504 - 3620	Lime
3620 - 3710	Lime
3710 - 3720	Conglomerate
3720 - 3740	Viola
3740 - 3750	Lime
3750 - 3784	Chert and Shale
3784 - 3810	Shale and Sand
3810 - 3816	Shale
3816 - 3839	Shale and Lime
3839	<u>Rotary Total Depth</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1971
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, E. K. Edmiston, President of the E. K. Edmiston Drilling Company, Inc., hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.


E. K. Edmiston Drilling Co., Inc.
 By *[Signature]*
 E. K. Edmiston, President

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

Be it remembered, that, on this 21st day of December, 1962, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument as President and in behalf of the E. K. Edmiston Drilling Company, Inc. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires: 4-23-63 *[Signature]* (Notary Public)



STATE OF KANSAS
STATE CORPORATION COMMISSION-CONSERVATION DIVISION
500 Insurance Building-212 North Market
Wichita 2, Kansas

15-185-10909-0000

DATA AND AFFIDAVIT

(File one Copy)

(On Cementing In Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137, and 55-138, 1947 Supplement to G. S. Kansas 1935)

Lease Owner E. K. Edmiston

Office Address 501 First National Bank Building, Wichita, Kansas

Lease Name Dudrey Well No. 1

Well Location (Example: C N/2 NE/4 NE/4 or footage from lines)

SE SE NW SEC 21 TWP 22S RGE 13W(E) County Stafford

Contractor E. K. Edmiston Drilling Company, Inc.

Office Address 501 First National Bank Building, Wichita, Kansas

Drilled with (cable) (Rotary) tools: Date pipe set 12-9 19 62

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 12 1/4" Csg. (New) (Used) Size 8 5/8" Wt. 24#

Depth 250' Where set 250'

METHOD OF CEMENTING

(a) Cement: Amount and kind 250 sacks Sunset (quick drying)

Method: (By Service Co., Dump, Tog., etc.) service co.

Est. Height Cement behind pipe circulated

(b) Cementing Material: Explain method. (Example: 8-5/8 w/swag nipple run inside 15", Bridge hold 2/rock and hole filled with cementing material, 15" pipe pulled.)

Describe cementing material quick drying cement

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum 50'

Name of lowest fresh water producing stratum unknown

Surface elevation of well 1906 KB

ADDITIONAL INFORMATION

(Additional Information may be submitted on separate sheet)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,
I, E. K. Edmiston, of the E. K. Edmiston Drilling Company, Inc.
first duly sworn on oath, state: That I have knowledge of the facts,
statements and matters herein contained and that the same are true
and correct.

Subscribed and sworn to before me on this 21st day of Dec. 19 62
My Commission Expires:

April 23, 1963

Juanita M. Green
Juanita M. Green, Notary Public