

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued February 13, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
2-21-68

Operator's Full Name T. O. Gaskill, c/o Clark T. Snider  
 Complete Address: 514 Union Center Bldg., Wichita, Kansas 67202  
 Lease Name Durham Well No. # 1  
 Location NE NW NE Sec. 22 Twp. 22 Rge. 12 (E) (W) W  
 County Stafford Total Depth 3678'  
 Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
 Other well as hereafter indicated:       
 Plugging Contractor: Southwest Casing Pulling Company  
 Address: Box 364, Great Bend, Kansas 67530 License No. 399  
 Operation Completed: Hour 11:15AM Day 20th Month February Year 1968

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 225 sacks. 3674' of 5 1/2" long string,  
cemented with 125 sacks. Plug back T.D. 3638'. Top perferation 3435'. Bottom  
of the hole was sanded to 3400', and cemented with 5 sacks, through the dump  
bailer, with cement from 3400' to 3360'. 2750' of 5 1/2" long string was recovered  
from the hole. Surface pipe had a hole at 65', and was squeezed. 10 sacks of  
Gel-Mud with 1 sack of hulls, and 100 sacks of cement was pumped into the sur-  
face pipe, through an 8 5/8" swage, to a pressure of 100 lbs, with cement from  
270' to the base of the cellar. A wiping plug was run between the mud and the  
cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 2/21/68

INV. NO. 7297-W