

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION  
Wichita, Kansas

6-20-74

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pate-Dombaugh Petro & Martin Exploration

Complete Address 502 Union Center, Wichita, Kansas

Lease Name Hey Well No. A-1

Location C NE SE Sec. 28 Twp. 22 Rge. 25 (E) (W)

County Hodgeman Total Depth 4142'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor B&B Drilling Co.

Address 720 Union Center, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00Pm Day 16 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 385' circulated w/ cement. Mud 4142' to 800' ~~XXXXXX~~

Spotted 35 sacks cement 800' to 700' Mud 700' to 385'

Spotted 35 sacks cement 385' to 285' Mud 285' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Allied Pump Truck

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 6/24/74

INV. NO. 9366-W

Signed: [Signature]  
Well Plugging Supervisor