

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 138-22

LOCATION Nw-Nw-NE

SEC. 21 TWP. 22 RGE. 12w

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Ukens

Operator Standard Oil & Gas Co. Address Box 1654 Okla. City, Okla.

Field _____ County Stafford

Total Depth 3692 Feet.

Plugging Contractor R & S Pipe Pulling Co.

Plugging Contractor's License No. 1

Address Callinwood, Kansas
(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 656' l.w.c. 5 1/2" set 3689'
4 1/2" 25' l.w.c. Sanded hole to 3680' dumped
5' l.w.c. shot off and pulled 5 1/2" casing
mudded hole to 275' set rock bridge
and dumped 20' l.w.c. mud to 35' rock
bridge and 10' l.w.c. to base of cellar.

Warren H. Horner
District Conservation Agent

Date Aug 18, 1955

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1955
CONSERVATION DIVISION
Wichita, Kansas
8-22-55

PLUGGING
FILE SEC 21 T 22 R 12W
BOOK PAGE 137 LINE 22