

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1966

CONSERVATION DIVISION
WICHITA, KANSAS

7-7-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Glickman Oil CompanyComplete Address: Box 11104, Wichita, KansasLease Name Grett Well No. # 1Location SE NE NE Sec. 21 Twp. 22 Rge. 12 (X) (W) WCounty Stafford Total Depth 3694'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling CompanyAddress: 1450 Maple, Russell, Kansas License No. 9Operation Completed: Hour 11:45 AM Day 1st Month July Year 1966

The Above well was plugged as follows:

261' of 8 5/8" surface pipe, cement circulated. 3692' of 5 1/2" long string,
cemented with 75 sacks. This is an open hole. Bottom of the hole was sanded
to 3670', and cemented with 5 sacks, through the dump bailer. 3005' of 5 1/2"
long string was recovered from the hole. Bridge plug was pushed in fluid to
250', rock bridge from 250' to 240'. 5 sacks of cement was mixed in a barrel,
and put on plug at 240', through the dump bailer. Next day hole was bailed
dry, and filled with 3 1/2 yards of ready-mix cement, from 225' to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-7-66INV. NO. 3523-W